

	IMM Range (ton)	Payload (kg)	Vertical (mm)	Crosswise (mm)	Max Reach (mm)
XQ-450V	30-80	2	450	75	350
XQ-600V	80-180	2	600	75	350
XQ-800V	160-350	2	800	75	450

Optional Features

Vacuum Confirmation Unit Air Nipper in Chuck Defective Product Reject Circuit Chuck Twist (C Type) Custom Paint Color

Stec-S1 Controller



Screen Size

3.25" High Contrast LCD

Axis of Operation

Capable of controlling up to 5 pneumatic axis

Inputs

- 14 Standard Inputs (Factory)
- 4 Spare Inputs Available For Customized Programming Use (Factory)

Outputs

- 16 Standard Outputs (Factory)
- 6 Spare Outputs Available For Customized Programming Use (Factory)

Timers

12 Standard, 5 Option, 7 Alarm

Axis Setting Points

Mechanically Limited Pneumatic Strokes

Counters

1 Total, 1 Option, 1 Product

Memory

Internal Memory (up to 15 molds Setups)

Star Automation, Inc. N90W14401 Commerce Dr Menomonee Falls, WI 53051







